



NOTES:

SECTION A-A

1. REPLACE ENTIRE PANEL OF FULL WIDTH SIDEWALK TO NEAREST CONTROL JOINT.
2. PORTLAND CONCRETE CEMENT MIX SHALL BE PER GREENBOOK (SSPWC), 520-C-3250.
3. COMPACTION OF NATIVE SUBGRADE SHALL MEET 90%, UNLESS SPECIFIED OTHERWISE BY THE CITY ENGINEER.
4. WEAKENED PLANE JOINTS SHALL BE CONSTRUCTED PER GREENBOOK (SSPWC) SECTION 303-5.4.3, AT REGULAR INTERVAL NOT EXCEEDING 10 FEET.
5. MATCH SCORING PATTERNS OF ADJACENT SIDEWALK. ROUGH FINISH SCORING PATTERNS REQUIRED IN AREAS NEAR BEACH ACCESS POINTS.



CITY OF LAGUNA BEACH PUBLIC WORKS DEPARTMENT

REV.	DATE	SIDEWALK		STANDARD PLAN
		APPROVED BY:	03/29/2022	107
		MARK A. TRESTIK, CITY ENGINEER, R.C.E. 53708	DATE	1 OF 1